

FABRICATION PLANT'S CAPABILITIES

	<i>C/R</i>	<i>Monroe</i>	<i>Mansfield</i>	<i>Renton</i>
Pipe Cutting:				
Machine Cut	1/2"-12"	1/2"-8"	1/2"-12"	1/2"-12"
Torch Cut	24"	24"	24"	24"
Pipe Threading:				
Schedule 40	1/2"-12"	1/2"-8"	1/2"-8"	1/2"-12"
XL	1"-3"	1"-3"	1"-3"	1"-3"
Schedule 80	1/2"-12"	1/2"-8"	1/2"-8"	1/2"-12"
Brass/Copper	1/2"-12"	1/2"-8"	1/2"-8"	1/2"-12"
Grooving:				
Roll Grooving	1"-24"	1"-24"	1"-24"	1"-24"
Cut Grooving	1"-12"	1"-8"	1"-12"	1"-12"
Fitting Make-On	1/2"-12"	1/2"-8"	1/2"-12"	1/2"-12"
End Prep	1"-2"	1"-2"	1"-2"	1"-2"
Hole Drilling	All	All	All	All
Galvanized Welding	All	All	All	All
Stainless Steel:				
Threaded	1/2"-4"	1/2"-4"	1/2"-4"	1/2"-4"
Welded	Tig-Mig	Mig	Mig	Tig-Mig
Header Welding	All	All	All	All
Cut Groove Ductile Pipe	1"-12"	1"-8"	1"-8"	1"-12"
Cut Groove CPVC Pipe	1"-12"	1"-8"	1"-8"	1"-12"
Special Hangers	All Types	All Types	All Types	All Types
Pipe Painting	Subcontract	Subcontract	Subcontract	Subcontract